

Energy Procurement & Renewable Strategy 2026-2030

Data Centre Portfolio · Data Centre · Singapore & Europe

Document ID	DC-06
Category	Sustainability Strategy
Classification	Strategic
Date	2026-01
Prepared by	Data Centre Fund Management

1. Context

The data-centre portfolio consumes about 420 GWh of electricity per year. Energy is 45-60% of operating cost, and hyperscale customers now require renewable-energy matching and declining carbon intensity in new contracts. Without action, rising tariffs and carbon prices will erode margins and win rates.

2. Strategy pillars

- Efficiency first: reach a portfolio PUE of 1.40 through containment, higher operating temperatures and plant-level chiller optimisation. Proven chiller-plant optimisation practices elsewhere in the wider real-estate portfolio should be evaluated for data-centre plants.
- Renewable procurement: corporate PPAs for wind power in Ireland; renewable energy certificates (RECs) and regional electricity imports in Singapore as they become available.
- On-site solar: limited roof area means on-site solar covers only 1-2% of load, but it is visible to customers.
- Heat reuse: pilot the export of waste heat to a district heating network in Dublin.
- Green financing: link sustainability-linked loans to PUE and renewable-share targets.

3. Targets and roadmap

KPI	2025	2027	2030
Portfolio PUE	1.58	1.48	1.40
Renewable electricity share	18%	35%	60%
Carbon intensity (kgCO ₂ e per kWh of IT load)	0.52	0.38	0.22

4. Investment envelope

The plan requires about S\$85 million over five years: S\$40 million for efficiency retrofits, S\$25 million for on-site solar, heat reuse and electrical upgrades, and S\$20 million of contingency and PPA collateral. Efficiency projects are expected to pay back in 3-5 years; renewable procurement is expected to be cost-neutral to slightly positive over the PPA terms.

5. Key risks

- Availability and price of renewable electricity in Singapore.
- Customer acceptance of higher operating temperatures.
- Execution capacity of engineering teams while facilities remain live.